

BID SCHEDULE						
DRIVEWAY ACCESS IMPROVEMENTS						
COLORADO MOUNTAIN COLLEGE- RIFLE CAMPUS						
SE PROJECT # 15206					2/17/2016	
Item No.	Description of Work	Unit	Estimated Quantity	Unit Price	Total Price	Total Price (Words)
General:						
G1	Mobilization/Demobilization: Not to exceed 5% of subtotal for entire project, per lump sum.	JOB	LS			
G2	Traffic Control: Traffic control plan, barricading, signage, materials, labor and equipment necessary for completed project, per lump sum.	JOB	LS			
G4	Erosion and Sediment Control: Additional Erosion and Sediment Control BMP's (Dust Control, etc.), per lump sum.	JOB	LS			
SUBTOTAL OF ITEMS G1-G4:						
Site Demolition:						
D1	Removal of Concrete: Concrete to be sawcut and removed from site, disposed of at an appropriate location, per square yard.	SY	565			
D2	Sawcut and Removal of Asphalt: Asphalt to be sawcut at 2 foot min or as needed for smooth straight neat sawcut line and removed from site, disposed of at an appropriate location, per square foot.	SF	270			
D3	Sawcut and Removal of Concrete Curb and Gutter and Valley Pan: Curb and Gutter and Valley Pan to be sawcut and removed from site, disposed of at an appropriate location, per linear foot.	LF	100			
D4	Sawcut and Removal of Concrete Sidewalk: Sidewalk to be sawcut at nearest joint and removed from site, disposed of at an appropriate location, per square foot.	SF	81			
SUBTOTAL OF ITEMS D1:						
Road and Asphalt Trail Improvements:						
S1	Subgrade Preparation: Provide all labor and equipment to remove the subgrade at a depth of 24", per square yard.	SY	565			
S2	Triax TX140 Geogrid: The geogrid to be placed on top of angular material flat, including furnishing, placing, and complete in place per square yard. (Note the square yard does not include the required overlap per the manufacture recommendations.)	SY	565			
S3	Angular rock: Provide 1.5" cleaned angular rock (crushed material, place on subgrade and rake to uniform smooth surface for placement of geogrid: including furnishing, haulers and placing, and complete in place per cubic yard.	CY	32			
S4	Class 2 ABC: Class 2 ABC subgrade to be place on top of geogrid, 12 inch depth including furnishing, hauling, placing and compacting, complete and in place, per cubic yard.	CY	190			
S5	Class 6 ABC: Class 6 ABC subgrade to be place on top of Class 2, 10 inch depth including furnishing, hauling, placing and compacting, complete and in place, per cubic yard.	CY	158			
S6	SX75 Asphaltic Pavement: Asphalt pavement to placed in two lifts, to install a 5" thick pavement, including furnishing, hualing, placing and complete in place, per square yards.	SY	580			
S7	Concrete Curb and Gutter: Concrete curb and gutter to be furnished and replace sections of curb and gutter that was removed, per linear foot.	LF	247			
S8	Concrete Sidewalk: 6" concrete sidewalk to be furnished and smooth dowels to be lubed and drilled 18" on center into existing concrete sections and replace sections of removed sidewalk sections, per square foot.	SF	152			
S9	Concrete Valley Pan: Valley Pan to be furnished and replace the section removed in kind, per square foot.	SF	216			
SUBTOTAL OF ITEMS S1-S9:						
TOTAL OF ALL ITEMS:						

Subcontractor List

- 1 _____
- 2 _____
- 3 _____
- 4 _____