



RFP #781-18 Edwards Parking Lot Overlayment

Addendum 001 Issued February 27, 2018

1. Can we get a proposed quantity and mix design for the Asphalt on this project?
 - a. Assuming SX 75 PG 58-28
 - b. Initial takeoff area was about 120,000

This assumption is correct.

2. With regard to traffic control, will we be able to close all of the proposed work areas to traffic?
 - a. Assuming that all work areas will be free of vehicles and able to be closed to the public.

Yes. All work areas to be serviced can be sealed off to outside traffic. However, the areas of the parking lot that have already been completed will need to remain open for general parking.

3. What type/quantity of striping material is to be used?
 - a. Assuming waterborne paint (typical for parking lots)

We desire a product that can hold up to our Rocky Mountain winters including plowing, snow, ice and traffic.

4. There was some discussion during the walkthrough about possibly doing some crack filling after milling, before the overlay goes down. Should we include an item or alternate for crack filling? Can you provide a quantity to use?

Yes, please include a separate line item that includes the following: cost for crack filling/sealing all areas that need to be controlled after the 2" mill but before the final overlayment..