



RFP #786-18
Dillon Alternate Entry Addition

Addendum 001
Issued March 5, 2018

1. Drawing C-2, of the referenced project, has a note calling for “Sawcut Ex. Asphalt”. Are we removing and replacing the shaded area of asphalt? Please clarify.

The plan identifies the asphalt sawcut line, and also notes 'Remove asphalt and replace with concrete'. The removed asphalt allows the driveway apron to be regraded to allow for an ADA approved 2% cross slope crossing at the driveway.

2. Does this project require 3rd party testing? If so who is responsible for it?

Yes, this project will have 3rd party inspections on concrete, soil prep, and footings. Owner will contract with a company to perform this service. General Contractor will be required to work with owner to schedule 3rd party inspection times and dates.