



RFP #877-20P Sopris Hall Painting

**Addendum 002
Issued February 20, 2020**

Specifications in the RFP has been revised to include the following:

- Change paint #1 is to be Sherwin Williams Conflex XL. This is the stucco paint
- All caulk for cracks wider than an 1/16 of an inch shall be elastomeric caulk
- Owner will fix 2 spots on South end of building that are bad (see pictures)
- Each paint coat on stucco will be backrolled
- All windows and doors will be caulked with elastomeric caulk.